



KENYA URBAN ROADS AUTHORITY

Efficient and safe urban roads

Barabara Plaza, Mazao Road - Off South Airport Road, JKIA

Tel: 254-020-8013844 / 254-717-105233

Email: info@kura.go.ke Web: www.kura.go.ke

P.O. Box 41727-00100, GPO, NAIROBI

REF. NO. KURA/EO/SCM/Vol.3 (250)

Date: 14th April, 2020

TO ALL BIDDERS

RE: UPGRADING OF TOM MBOYA ROAD KISUMU COUNTY

TENDER NO: KURA/DEV/HQ/306/2019-2020

RE: ADDENDUM 1

Reference is made to the above subject matter.

This to notify all bidders that an addendum has been issued for the above tender as attached.

S/NO	AMENDMENT	ACTION
1.	BILL 1	Replace with attachment
2.	BILL 14	Replace with attachment
3.	BILL 20	Replace with attachment

Please note that the tender Opening Date/Closing still remains the same date of 30th April 2020 at 10.00 am

Saadia H. Adankhalif

Deputy Director, Supply Chain Management

FOR: Ag. DIRECTOR GENERAL

UPGRADING OF TOM MBOYA ESTATE AND ENVIRONS ROADS
TENDER No.: KURA/DEV/HQ/306/2019-2020

Item	Description	Unit	Quantity	Rate (KShs)	Amount (KShs)
BILL 1 - GENERAL					
1.01	Provide and maintain furniture and equipment for the Engineer's office as specified for the Contract period and as detailed in Appendix to Bill Item № 1.01.	PC Sum	1,000,000.00	1	1,000,000.00
1.02	Extra Over on Item 1.01 for the Contractors Overheads and Profit.	%	1,000,000.00		
1.03	Allow a sum of KShs 1,000,000.00 for the Engineer's miscellaneous account to be spent in whole or part as instructed by the Engineer and to be reimbursed against receipts.	PC Sum	1,000,000.00	1	1,000,000.00
1.04	Extra Over on Item 1.03 for the Contractors Overheads and Profit.	%	1,000,000.00		
1.05	Allow a Prime Cost sum of Ksh. 500,000.00 for off-site materials testing by the Resident Engineer	PC Sum	500,000.00	1	500,000.00
1.06	Extra Over on Item 1.05 for the Contractors Overheads and Profit.	%	500,000.00		
1.07	Provide, erect and maintain publicity signs as shown in the drawings or as instructed by the Engineer.	№	2		
1.08	Allow for attendance upon the Engineer by the following staff in accordance with Clause 137 of Special Specification.				
	(a) Assistant Engineer	M. month	18		
	(b) Inspectors of Works	M. month	36		
	(c) Survey assistant	M. month	18		
	(d) Chainmen	M. month	36		
	(e) General Attendants	M. month	36		


07.04.2020

Item	Description	Unit	Quantity	Rate (KShs)	Amount (KShs)
1.09	Extra over item 1.08 (a) - (e) for Contractor's overheads and profits	%	1		
1.11	Provide with driver and maintain two (2), minimum 2.8 litre turbocharged 4-wheel drive, twin- cab pick-up vehicle or similar approved by the Engineer, fitted with air bags, mobile telephone hand free headset and a two way radio for the exclusive use of the Engineer inclusive of the first 4,000 km per vehicle month.	V. month	36		
1.12	Extra Over on Item 1.11 inclusive of fuels, maintenance, lubricants and servicing for kilometrage over 4,000 km per vehicle month.	km	6,000		
1.13	Provide with driver and maintain one (1) Type 3 vehicle, minimum 2.8 litre 4-wheel drive, single-cab pick-up vehicle (with canvas back seat) or similar approved by the Engineer, fitted with air bags, mobile telephone hand free headset and a two way radio for the exclusive use of the Engineer inclusive of the first 4,000 km per vehicle month.	Veh. Month	18		
1.14	Extra Over on Item 1.09 inclusive of fuels, maintenance, lubricants and servicing for kilometrage over 4,000 km per vehicle month.	Km	10,000.00		
1.15	Allow a Prime Cost sum of Ksh. 3,500,000.00 for payment of wages and allowances for Engineer's staff including overtime	PC Sum	3,500,000.00	1	3,500,000.00
1.16	Extra Over on Item 1.15 for the Contractors Overheads and Profit.	%	3,500,000.00		
1.17	Allow a Prime Cost sum of Ksh. 500,000.00 for payment for maintenance of Survey Equipments	PC Sum	500,000.00	1	500,000.00
1.18	Extra Over on Item 1.17 for the Contractors Overheads and Profit.	%	500,000.00		
TOTAL CARRIED TO SUMMARY PAGE					


07.04.2020

Item	Description	Unit	QUANTITY	Rate (KShs)	Amount (KShs)
BILL 14- CEMENT AND LIME TREATED MATERIALS					
14.01	Provide transport to site of works cement improvement agent for natural material base as specified or as instructed by the Engineer.	Tonne	236.49		
14.02	Mix and process natural material with cement as an improvement agent for base and compact at OMC to achieve the desired compressive strength as specified or as directed by the Engineer.	M ³	9,140		
14.03	Allow for curing and protection of cement treated base layer as specified or as instructed by the Engineer.	M ²	61,000		
TOTAL CARRIED TO BILL SUMMARY					


07.04.2020

Item	Description	Unit	QUANTITY	Rate (KShs)	Amount (KShs)
BILL 20 - Road Furniture					
20.01	Provide and lay hot applied thermoplastic road marking compound in approved colour and shade (ASTM 9) for road marking on bituminous surface on centerline, 100 mm, edge line 150 mm wide 3.0 mm thick, using fully automatic extrusion machine and using pre-melter for melting thermoplastic material including cleaning the surface of all dirt, dust, and other foreign matter, complete with demarcation at site/pre-marking, finishing and managing the traffic movements. Marking to be done as per the specifications, detailed drawings and as instructed by the Engineer.				
	(i) For lane marking (broken lines) with yellow paint, 100 mm wide.	M ²	400		
	(ii) For edge lines (continuous line) with white paint, 150 mm wide	M ²	1,800		
20.02	Provide all materials, excavate for and lay 250x125mm precast concrete class 20/20 raised straight / circular kerbs (to include concrete class 15/20 for bedding and haunching) as per specifications and as directed by the Engineer	M	6,000		
20.03	Provide all materials, excavate for and lay 100x125mm precast concrete channels (to include concrete class 15/20 for bedding and haunching)	M	12,000		
20.04	Provide and place approved road signs (Area <1m ²) as directed by the Engineer;				
	i) Warning Signs	N _o	20		
	ii) Priority, Prohibitory and Mandatory signs	N _o	20		
	iii) Standard Informatory Signs	N _o	20		
20.05	Place and provide gauge 16 steel pipe Bollards of diameter 150mm and 1.0 m above the ground, embedded to a depth of 0.5m at place painted and fitted and refrectozed as shown on the drawing and as directed by the Engineer. Rate to include filling with concrete minimum class 15/20	M	60		


07.04.2020

UPGRADING OF TOM MBOYA ESTATE AND ENVIRONS ROADS
TENDER No.: KURA/DEV/HQ/306/2019-2020

Item	Description	Unit	QUANTITY	Rate (KShs)	Amount (KShs)
20.06	Provide and install retro-reflective reflective road studs (cat's eyes) as per the drawings and as instructed by the Engineer	N _o	900		
TOTAL CARRIED TO BILL SUMMARY					


07-04-2020